



NORMAL QUALITY

NO	ITEM	DESCRIPTION
1	bottom frame	beamthickness 2.5mm secondary purlin C120*60*1.7mm 50mm glasswool insulation 0.23mmcovering tile beamthickness 2.5mm Z molding part
2	top frame	secondary purlin 80*40*1.3mm 50mm glasswool insulation+PE film 0.5mm steel sheet

3	column	2526*210*150*2.5mm
4	floor board	18mm fiber cement board
5	floor covering	1.6mm PVC vinyl flooring
6	steel door	T75 0.6mm,size 845*2035
7	PVC window	pvc sliding window 1130*1100 double glasses,flying screen
8	wall panel	V1150,75mm glasswool sandwich panel0.4/0.450KG/m ³ φ50mmPVC pipes 831*0.4mm ceiling 75 channel
9	Accessories	PVC skirting 0.4mmcolumn cladding rivet,screw,glue,etc.
10	Electric	Industry plug,distribution box,4 socket,1switch,2 light

FAQ

1, What's your Payment term?

50% deposit by TT, 50% balance before loading container by TT; 100% LC at sight total payment over 100,000USD);

2, How about Shipping?

We use 40HQ container to ship the goods; Usually 40HQ container can load about 160-180square meters house.

3, Delivery time?

Depend on MOQ,usually we can arrange shipment around 10days after received deposit

4, How to install?

Usually we will provide installation drawing,and if necessary,we also provide installation video.

5, Can you send workers to help me build house?

Considering the labor cost, safety and visa issues, we suggest to send one or two engineers to guide and train your staffs. You must provide air tickets, hotel, and meal, and 100USD per day for engineer salary.