



Delivery by 40'HQ shipping container by bulk packing in general .

Packaging Mixed packaging: roof frame and bottom frame will be packed together with bolts; all the wall panels packed together with wooden pallet in the bottom, corrugated board on the surface, and XPS board in the interspace. And it will be shipped in 40' container .

40 feet ocean freight container:

A: Take out the small packages.

B: Use folk lift to take out the wall panel packages.

Unloading

C: Grapple the corner on bottom side of the container house and drage the package out,remain about 50cm in the shipping container.

D: Use folk lift to lift the container package in the middle and move it out of the shipping container.

E: Put the package on ground sidewise, use wooden pad if it's flatwise.