



## BREAKDOWN QUOTATION SHEET

PROJECT	6000mm*2400mm*2896mm combined modular container			
NO. NAME	DESCRIPTION	SIZE	QTY	UNIT
□ BASIC ITEM			9	set

		color steel buckle plate	0.5mm		
<b>1</b>	Roof	glasswool insulation		9	set
		galvanized steel keel			
		white metal ceiling	0.3mm		
		vinyl leather flooring	1.6mm		
<b>2</b>	Floor	cement fiber board	1.8mm	9	set
		PE insulation film			
		galvanized steel keel			
<b>3</b>	Column	galvanized steel column	L2580mm	36	pc
<b>4</b>	Drain pipe	Rain drain pipes	white pvc pipe	36	pc
<b>□ INCREASE ITEM</b>					
<b>5</b>	Wall panel	75mm Glasswool sandwich panel		281.7	□
<b>6</b>	Exterior wall decoration	Hanging board		191.4	□
<b>7</b>	Pergola	Anticorrosive decoration wood		0	m
<b>8</b>	Decking	WPC		43.2	□
<b>9</b>	Guardrail			25.2	□
<b>10</b>	Stair			1	set
<b>11</b>	Window	Aluminium-alloy window		38	□
<b>12</b>	Door	white steel door	800mm*2000mm	5	set
		Aluminium-alloy door		14.6	□
		change into local standard		9	set
<b>13</b>	Electric system	Led light		12	pc
		switch		12	pc
		socket		15	pc
<b>14</b>	Water system	inlet & outlet water pipes		28.05	□
		PVC cover skirting		9	set
		Connection	module connection lock	38	set
			module top and column connection part covering	105.6	m
<b>15</b>	Assemble Accessories	Molding covering	module floor connection part covering	39.6	m
		sealing tape	rubber tape filling between module connection part	72.6	m
		Self-glue tape	waterproof self glue tape between module connection part	67.8	m

	shower		set
	toilet		set
<b>16</b>	Facilities(option)	basin	set
		bed	set
		table	set
		wardrobe	set

**Total Amount (Necessary Basic Fitting)**

<b>15</b>	Inland Cost	40HC container loading	2	pcs
		20GP container loading	0	pcs
<b>16</b>	Workers loading Cost	40ft/20ft container	2	pcs

**TOTAL AMOUNT(EXW PRICE)-**