



## Delivery by 40'HQ shipping container by bulk packing in general.

Packaging	Mixed packaging:roof frame and bottom frame will be packed together with bolts;all the wall panels packed together with wooden pallet in the bottom,corrugated board on the surface,and XPS board in the interspace. And it will be shipped in 40' container .
Unloading	40 feet ocean freight container:
	A: Take out the small packages.
	B: Use folk lift to take out the wall panel packages.
	C: Grapple the corner on bottom side of the container house and drage the package out,remain about 50cm in the shipping container.
	D: Use folk lift to lift the container package in the middle and move it out of the shipping container.
E: Put the package on ground sidewise, use wooden pad if it's flatwise.	