Описание товара

Heya-2S09





QUOTATION SHEET							
NO.	Heya-2S09		DATE				
NO	ITEM	DESCRIPTION	UNIT	THEORY QTY	LOSS RATE	UNIT	ACTUAL QTY
Frame System							
1	Steel structure		m^2	104.00	1.00	T	4.16
2	Fittings		set	104.00	1.00	m^2	104.00
Wall System							
3	External wall foamed cement board	610*2270*T90mm	m^2	185.60	1.10	pc	148.00
4	Internal wall foamed cement board	610*2270*T60mm	m^2	48.30	1.10	pc	39.00
Roof System							
5	Roof panel	75mm EPS sandwich panel	m	135.40	1.10	m	148.94
Door & Window System							
7	PVC window		m^2	9.12	1.00	m^2	9.12
8	PVC door		m^2	10.80	1.00	m^2	10.80
Decoration System							
9	Ceiling	gypsum board,600*600mm 10pcs/pack	m^2	104.00	1.10	pack	12.00
10	Floor tile	ceramic tile 600*600mm 10pcs/pack	m^2	104.00	1.10	pack	12.00
11	Internal Putty	Brand:Nippon 15kgs/bag	m^2	282.20	1.10	bag	21.00
12	Internal wall coating	white,18L/bucket	m^2	282.20	1.10	bucket	4.00
13	External wall coating	16L/bucket	m^2	185.60	1.10	bucket	3.00
Water&Electric System							
14	Drain pipes ,gutter		n	43.00	1.00	m	43.00
15	Water Pipes	inlet & outlet pipes	m^2	104.00	1.00	m^2	104.00
16	Electric system	Include weak current,exclude socket/switch/light,etc	m^2	104.00	1.00	m^2	104.00
Hardware Accessories System							
17	Hardware Accessories System		m^2	104.00	1.00	m^2	104.00
Fitting facilities							
18	Toilet		pc	0.00	1.00	pc	0.00
19	Basin		pc	0.00	1.00	pc	0.00
20	Shower		pc	0.00	1.00	pc	0.00
21	Kitchen Cabinet		m	0.00	1.00	m	0.00
Inland Transportation							
22	Inland cost	loading fee,truck transport,custom declare,port charges,etc.	nos				1.00
TOTAL PRICE (FOB Qingdao)			**$17,281.21**				