

□□□□□□□□□□□□□□□□

Heya-2Q08



PROJECT NO.	HY-2-Q08	DATE				
NAME	DESCRIPTION	UNIT	THEORY QTY	LOSS RATE	UNIT	ACTUAL QTY
LGS Structure						
steel structure		m ²	91	1	T	3.00
fitings		set	91	1	m ²	91.00
Wall System						
External wall OSB board	1220*2440*9mm	m ²	167.185	1.15	pc	66.76
External wall unidirectional breath paper		m ²	175.165	1.2	m ²	210.20
External wall metal carved board	381*3800*16mm → 381*4500*16mm	m ²	167.185	1.15	m ²	192.26
Internal wall OSB board	1220*2440*9mm	m ²	197.967	1.12	pc	76.99
Internal wall gypsum board	1200*2400*9mm	m ²	197.967	1.12	pc	76.99
Wet district fiber cement board	1220*2440*10mm	m ²	73.524	1.12	pc	28.59
Insulation System						
Glasswool insulation	T75mm, 12 m ² /roll 16Kg/m ³	m ²	219.338	1.1	roll	20.11
Glasswool insulation(under roof)	T75mm, 12 m ² /roll 16Kg/m ³	m ²	107.2	1.1	roll	9.83
External wall XPS board	1200*600*40mm	m ²	167.185	1.05	pc	243.81
Roof System						
Roof OSB board OSB	1220*2440*12mm	m ²	134.68	1.15	pc	53.78
self-paste waterproof coil	T1.5mm, -15°C, 20 m ² /roll	m ²	134.68	1.2	roll	8.08
Roof tile	asphalt tile	m ²	134.68	1.2	pack	57.72
Roof ridge tile	asphalt tile	m	14.15	1.1	pack	1.95
Roof eaves pre molding PVC	6m/pc	m	50.5	1.1	pc	9.26
PVC closing strip PVC	4m/pc	m	50.5	1.1	pc	13.89
Metal carved board under roof eaves	381*3800*16mm	m ²	25.25	1.2	pc	21.04
Door & Window						
PVC window		m ²	7.98	1	m ²	7.98
PVC door		m ²	10.8	1	m ²	10.80
Accessories for door sill/window sill	1220*2440*10mm	m	59.5	1.1	pc	4.55
Water&Electric System						
Water Pipes		m ²	91	1	m ²	91.00
Electric system	Include weak current, exclude socket, switch, light, etc.	m ²	91	1	m ²	91.00
Decoration Accessories System		m ²	91	1	m ²	91.00
Hardware Accessories System		m ²	91	1	m ²	91.00
TOTAL EXW cost				\$16,948.89		
TOTAL FOB QINGDAO				\$17,848.89		
TOTAL CIF XX				\$19,938.13		



